

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR
FORMATION PLUGGING RECORD


Strike out upper line
when reporting plug-
ging of formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Pratt County, Sec. 22 Twp. 26 Rge. (E) 13 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. SE SE NW
Lease Owner. Mid-Continent Petroleum Corporation
Lease Name. E.F. Tolman Well No. 1
Office Address. Wichita 1, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed. April 30, 1948
Application for plugging filed. Verbal request, April 30, 1948
Application for plugging approved. April 30, 1948
Plugging commenced. April 30, 1948
Plugging completed. May 1, 1948
Reason for abandonment of well or producing formation. Did not produce

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production. 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well. Mr. C.D. Stough. Great Bend, Kansas.
Producing formation. Depth to top. Bottom. Total Depth of Well. 4633' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Lansing Lime	dry	3802'	4160'	8 5/8"OD	271'	None
Viola Lime	"	4141'	4525'			
Arbuckle Lime	Water	4588'	4633'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with heavy mud from 4633' to 270', Lane Wells bridging plug set at 270'.
Hole cemented with 15 sacks of cement through drill pipe from 270' to 225'.
Hole filled with heavy mud from 225' to 35' and wooden plug drove to 35' and cemented with 10 sacks of cement from 35' to 5' (bottom of cellar) Cellar to be filled to ground level.

Lloyd Snyder
5-6-48



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Mr. Lloyd Snyder
Address. Box 1362, Wichita 1, Kansas.

STATE OF Kansas COUNTY OF Barton, ss.


(employee of owner) or (owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) *R. E. Johnson*
Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 4th day of May, 1948.

Thos. Shetty
Notary Public.

My commission expires Oct 28-1948



DISTRICT OFFICE
MAY 6 1948
Wichita, Kansas

COMPANY - Mid-Continent Petroleum Corp.
WELL - E. F. Tolman No. 1

Sec. 22 T. 26 R. 13W
SE 1/4

Total Depth - 4633'
Comm. - 3-30-48 Comp. 4-30-48
Shot or treated
Contractor - Barnett Drilling, Inc.

COUNTY - Pratt

Elevation 1933

CASING:
8 5/8" 24" S.H. L. W. 268'

Production Dry

Clay	0	25
Sand & gravel	25	165
Red bed & shells	165	795
Sandy lime	795	817
Lime, Anhydrite	817	830
Shale & shells	830	1710
Shale & lime	1710	1825
Shale	1825	1850
Lime	1850	2020
Lime & shale	2020	2820
Shale	2820	2965
Lime & shale	2965	3035
Shale	3035	3060
Shale & lime	3060	3685
Sand, Douglas	3685	3740
Shale	3740	3802
Lime, Lansing	3802	4160
Cherty lime & shale	4160	4270
Conglomerate	4270	4389
Shale, lime & chert	4320	4441
Lime, Viola	4441	4525
Sandy lime & shale	4525	4588
Lime, Arbuckle	4588	4633
Total Depth	4633	

SCHLUMBERGER TOPS

Lansing	3802
Viola	4441
Arbuckle	4588

MAY 7 - 1948

PLUGGING
FILE 30-221-767(30)
26-31