

To: 040260
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 4748

Operator: A & A Discovery, Inc.

Name & Address P.O. Box 156

Hill City, KS 67642

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 12 p.m. Day: 6 Month: 4 Year: 19 89

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 4 1/2" at 4400' PBD 3900' Perfs at 3699-3702'

1st plug sand back to 3650' and dump 4 sx cement on top of sand through bailer,

2nd plug 10 sx gel, 60 sx cement, 12 sx gel, 1 sx hulls and 130 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 11 1989

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:30 p.m. Day: 6 Month: 4 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 3650' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped down 10 3/4" surface pipe with 400 lbs. hulls, 10 sx gel, 60 sx cement, 10 sx gel, 100 lbs. hulls, and 130 sx cement.

Plate and 2" collar welded in top of 10 3/4" surface pipe to pump through.

Maximum pressure 600 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2338' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

(X)(X)(X)(X) observe this plugging.

DATE 4-24-89

INV. NO. 24439

4-6
API NUMBER 15- 151-21,905-00-00
NE SW NW, SEC. 16, T 27 S, R 11 W/R
3630 feet from S section line
4290 feet from E section line
Lease Name Dietz "A" Well # 1
County Pratt 14300
Well Total Depth 4400 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 247

Signed Stephen J. Pfeifer
(TECHNICIAN)