

1 040458

9-6

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,367-00-00

C NE NW, SEC. 19, T 27 S, R 11 W 1/2

TECHNICIAN'S PLUGGING REPORT

Operator License # 5506

4620 feet from S section line

3300 feet from E section line

Operator: Woolsey Petroleum Corporation
Name & Address 107 N. Market, #600
Wichita, KS 67202

Lease Name Lehrling-Daughters Well # 2

County Pratt 149.50

Well Total Depth 4600 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1005

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:30 a.m. Day: 6 Month: 9 Year: 19 90

Plugging proposal received from Ronnie Hoover

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 4599' w/225 sx cement, Perfs at 4361-66'

1st plug sand back to 4310' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 6 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4310' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3200' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

SEP 18 1990
CONSERVATION DIVISION
Wichita, Kansas

~~(Do not observe this plugging.)~~

INVOICED

Signed Stephen J. Pipe
(TECHNICIAN)

DATE 9-25-90

INV. NO. 29432

9-6