

1041339
TO: STATE CORPORATION COMMISSION

2-10

API NUMBER 15-151-20,968-00-00
180'N SW NE SEC. 19, T 27 S, R 11 W

CONSERVATION DIVISION - PLUGGING SECTION 1800 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME LEHRLING DAUGHTERS WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY PRATT 145.83

OPERATOR LICENSE # 5506

WELL TOTAL DEPTH 4487 FEET

OPERATOR: WOOLSEY PETROLEUM CORPORATION PRODUCTION CSG: SIZE 5 1/2" @ 4444' WITH 380 SX

NAME AND PO BOX 168 SURFACE CASING: SIZE 8 5/8" @ 880' WITH 475 SX

ADDRESS MEDICINE LODGE, KS 67104 CONDUCTOR CSG: SIZE 13 3/8" @ 215' WITH 275 SX

ABANDONED OIL WELL GAS WELL INPUT WELL _____ SWD WELL _____ D/A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR CLARKE CORPORATION LICENSE NUMBER 5105

ADDRESS PO BOX 187, MEDICINE LODGE, KS 67104

COMPANY TO PLUG AT: HOUR: 1:15 PM DAY: 10 MONTH: 02 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM ALAN VRATIL

(COMPANY NAME) CLARKE CORPORATION (PHONE) 316-886-5665

WERE: PERFS AT 3313-16, CIBP @ 3350' PERFS @ 3612-16 CIBP @ 3720 PERFS @ 3732-4030 OVERALL CIBP @ 4190 PERFS @ 4354-4361 OVERALL.

SAND TO 3263'. PLACE 5 SX ON TOP W/BAILER. CUT AND LAY DOWN 5 1/2" CASING. DOWN 8 5/8" WIPER PLUG AND 100 SX CEMENT. TOP OFF SURFACE IN 24 HOURS.

RECEIVED
COMMISSION

FEB 22 1999

PLUGGING PROPOSAL RECEIVED BY STEVE DFEIFER
Chile, Kansas

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 2:00 PM DAY: 10 MONTH: 02 YEAR: 1999

ACTUAL PLUGGING REPORT _____

1ST PLUG SANDED BACK TO 3220' AND PUT 15 SX CEMENT ON TOP OF SAND BRIDGE THROUGH BAILER.

2ND PLUG PUMPED DOWN 8 5/8" WITH 300# HULLS, 10 SX GEL, 50 SX CEMENT, 10 SX GEL, 100# HULLS,

8 5/8" WIPER PLUG, AND 100 SX CEMENT. MAXIMUM PSI = 700#. SHUT IN AT 600#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1940' OF 5 1/2" CASING.

NOTE: DUG OUT 8 5/8"/13 3/8" ANNULAS. FOUND PACKED W/CUTTINGS AT TOP. SUSPECT CEMENT NEAR SURFACE ON BACKSIDE OF 8 5/8"/13 3/8" ANNULAS.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DIE) OBSERVE THIS PLUGGING.

DATE 3-1-99

SIGNED Stephen J. Pfeifer (TECHNICIAN) FORM CP-2/3

INV. NO. 60672