

To: 1 040937 2-15
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
203 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,433-00-00

S/2 SW SW, SEC. 22, T 27 S, R 11 W/4
330 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5086
Operator: Pintail Petroleum, Ltd.
Name & Address: 225 N. Market, Ste. 300
Wichita, KS 67202

Lease Name Preisser Well # 1
County Pratt
Well Total Depth 3970 129.03 feet
Conductor Pipe: Size 10 3/4" feet 403
Surface Casing: Size 8 5/8" feet 720

Abandoned Oil Well Gas Well Input Well SMD Well O&A

Other well as hereinafter indicated _____

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 3:30 p.m. Day: 15 Month: 2 Year: 19 95

Plugging proposal received from Kevin Strube
(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

Work: 4 1/2" at 3968' w/150 sx cement, PBSD 3900', Perfs at 3878-85, 3767-70, 3647-53'
1st plug sand back to 3600' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement,
Check 8 5/8" X 10 3/4" annulus.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:30 p.m. Day: 15 Month: 2 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 3590' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" pipe surface with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 800 psi and shut in 600 psi.

Tied on to 8 5/8" X 10 3/4" annulus and pressured to 700#-held.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3000' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION
RECEIVED
FEB 25 1995
CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED (if applicable) observe this plugging.

DATE 2-28-95

Signed *Stephany Cooper* (TECHNICIAN)

INV. NO. 42291