



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JAN 2 1963

1-2-63
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dec. 18. 1962.

Dear Sir:

Mr. Ralph Glenn of Glenn & Smith Pipe Plug. Co. this
 date requested permission to plug the following described well:

Mr. Ralph Glenn guarantees payment of the plugging fee.

Operator's full Name: Champlin Oil & Refining Co.

Complete Address: Box 308 Ellinwood, Kansas.

Lease Name: Stueder #1 Well No. 1.

Location: SW-SE-SW Sec. 29 Twp. 26 Rge. 12 (E) (W) X

County Pratt Total Depth 4299' Abandoned Oil Well X and

Abandoned
 Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Ralph Glenn was instructed to plug the well as follows:

4299' of 5 1/2" oil string cemented with 250 sacks cement.
plugged back to 2446' Top perforation at 2413'. Sanded to
2400' & 5 sacks cement. 545' of 10 3/4" surface pipe circulated
with cement. Hole filled to 500' with heavy mud, 10' rock bridge
and 25 sacks cement. Hole filled to 40' with heavy mud, 10'
rock bridge & 10 sacks cement to base of cellar.

Very truly yours,

[Signature]
 Conservation Division Agent