

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

OCT 31 1962
 18-31-62
 CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Bill Musgrove of Musgrove Drilling & Petroleum Associates Fund has this Oct. 27 date requested permission to plug the following described well: 1962.

Mr. Bill Musgrove guarantees payment of the plugging fee.

Operator's full Name: Musgrove Drlg. & Petroleum Associates Fund

Complete Address: 801 Union Center Wichita, Kansas.

Lease Name: Hartsell #2 Well No. #2

Location: C-N $\frac{1}{2}$ - Lot 3 Sec. 3 Twp. 26 Rge. 12 (E) (W) X

County Pratt Total Depth 4259 Oil Well _____

Gas Well _____ Input Well _____ SWD Well _____ D & A X Lost Hole _____

Mr. Bill Musgrove was instructed to plug the well as follows:

390' of 8 5/8" surface pipe circulated with 275 sacks cement.
Hole filled to 160' with heavy drill mud, $\frac{1}{2}$ sacks balls,
1st cementing plug and 20 sacks cement. Hole filled to 40'
with heavy drill mud, $\frac{1}{2}$ sack balls, 2nd cementing plug, 10
sacks cement to base of cellar. Rat hole bridged and 2
sacks cement.

Very truly yours,

Herbert J. Gustus
 Conservation Division Agent