

State of Kansas



15-151-10934-00-02

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date 8 September, 19 58, authorized the following plugging operation:

Operator's Full Name: Forbes Casing Pulling Co.

Complete Address: Box 221, Great Bend, Kans.

Lease Name: Geissler Well No. 1

Location: NE NE NW Sec. 36 Twp. 26 Rge. 13 (E) (W) X

County: Pratt Total Depth: 4336

Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

8088 of 8 5/8" surface casing circulated with cement. Sand hole a above perf to 3955' and dump 5 sack cement with dump bailer. Lead hole with heavy mud and pull pipe. Heavy mud to 350' and set rock bridge. Place 20 sack cement top bridge. Heavy mud to 35' and set rock bridge and cement to base ofncellar.

Very truly yours,

Signed: [Signature] Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
SEP 20 1958
9-20-58
CONSERVATION DIVISION
Wichita, Kansas