

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY O. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 5 1936

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Dale Buller of Gabbert-Jones, Inc. has this date requested permission to plug the following described well:

Mr. Buller guarantees payment of the plugging fee.

Operator's full Name: Larsen-Madera-Harrison, c/o Gabbert Jones, Inc.

Complete Address: 830 Sutton Place, Wichita, Kansas

Lease Name: Mass Well No. # 1

Location: C NW NW Sec. 7 Twp. 27 Rge. 11 (E)(W) W

County Pratt Total Depth 4454 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Buller was instructed to plug the well as follows:

334' of 8 5/8" surface pipe, cement circulated with 275 sacks. Fill hole with drilling mud to 250', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent