

11-13-87

1 040007

API NUMBER 15- 151-21,422 - ~~0000~~

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NE NE, SEC. 6, T 26 S, R 12 (W) EX

4980 feet from S section line

1230 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5003

Lease Name Copenhaver Well # 2

Operator: McCoy Petroleum Corporation

County Pratt 137.64

Name & Address 110 South Main, Suite 500

Well Total Depth 4235 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 390

Abandoned Oil Well X Gas Well Input Well SHD Well O&A

Other well as hereinafter indicated

Plugging Contractor Hayes Well Service License Number 5429

Address Attica, KS

Company to plug at: Hour: 11:45 a.m. Day: 13 Month: 11 Year: 1987

Plugging proposal received from Daryl Hanson

(company name) McCoy Petroleum Corporation (phone) 316-532-5452

were: 4 1/2" at 4230' PBT 4189' Perfs at 4035-50, 3670-78'

1st plug set CIBP at 3650' with 4 sx cement on top of plug through bailer,

2nd plug pump 400 lbs. hulls and 140 sx econolight.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:05 p Day: 13 Month: 11 Year: 1987

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3650' and dumped 4 sx cement on top of plug through bailer,

2nd plug pumped down 8 5/8" surface casing with 400 lbs. of hulls and 140 sx lite cement.

RECEIVED STATE CORPORATION COMMISSION

Pumping pressure 200-500 psi and shut in 200 psi.

NOV 18 1987 11-18-87

Remarks: Used light cement by Halliburton. Recovered 2231' of 4 1/2" casing (if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION WICHITA, KANSAS

INVOICED (did not observe this plugging.)

Signed Stephen J. Pfeiffer (TECHNICIAN)

DATE 12-3-87

INV. NO. 19049 JAN 14 1988