

To: 1 041232 3-4  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-b51-20,881-0000  
NE NE NE, SEC. 6, T 26 S, R 12 W XX  
330 feet from NXX section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 30116  
Operator: Steve Jones  
Name: Steve Jones  
Address: 112 N. Gray  
St. John, KS 67576

Lease Name Copenhauer Well # 1  
County Pratt 140.56  
Well Total Depth 4325 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 358

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A   
Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529  
Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 2:45 p.m. Day: 4 Month: 3 Year: 19 97

Plugging proposal received from Steve Jones  
(company name) Steve Jones (phone) 316-549-6189

Work: 4 1/2" at 4323' w/225 sx cement, Perfs at 3675-81, 3814-24, 3870-72, 4040-56, CIBP @ 4200'  
4222-28'  
1st plug sand back to 3625' and dump 4 sx cement on top of sand through bailer,  
2nd plug at 750' with 50 sx cement,  
3rd plug at 390' with 50 sx cement,  
4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None   
Operations Completed: Hour: 4 p.m. Day: 4 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3619' and dumped 4 sx cement on top of sand  
bridge through bailer, Spotted plugs through 4 1/2" casing, gel spacer between plugs:  
2nd plug at 775' with 50 sx cement,  
3rd plug at 390' with 50 sx cement,  
4th plug at 80' with 20 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2014' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE 3-12-97  
INV. NO. 47726  
3-4

Signed Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 12 1997