

To: 1 050672
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,728-~~0000~~
NE SE SW, SEC. 7, T 26 S, R 12 W/E
990 feet from S section line

TECHNICIAN'S PLUGGING REPORT

2970 feet from E section line

Operator License # 5313

Lease Name Shandrew Well # 1

Operator: F + M Oil Co. Inc

County Pratt 154.70

Name & Address 422 Union Center

Well Total Depth 4420 feet

Wichita, Kansas 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Union Drilling Co. Inc License Number 5103

Address 422 Union Center Wichita, Kansas 67202

Company to plug at: Hour: 1:00 pm Day: 10 Month: November Year: 1985

Plugging proposal received from Lyle Casson

(company name) Union Drilling Co. Inc (phone) _____

were: To keep hole full of heavy mud + spot plugs

through drill pipe 1st plug @ 750' w/40sx cement

2nd plug @ 360' w/40sx cement

3rd plug @ 40' w/solid Bridge + 10sx

Circulate Rathole w/10sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:00 pm Day: 10 Month: November Year: 1985

ACTUAL PLUGGING REPORT Kept hole full of heavy mud + spotted plugs

through drill pipe 1st plug @ 750' w/40sx cement

2nd plug @ 360' w/40sx cement

3rd plug @ 40' w/solid Bridge + 10sx

Circulated Rathole w/10sx cement

Anhydrite @ 740' Elevation 1899 GL

Remarks: Halliburton pumped 60/40 poz mix 6% gel cement
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-9-85
INV. NO. 11328

observe this recording.
STATE CORPORATION COMMISSION
NOV 14 1985
11-14-85
CONSERVATION DIVISION

Signed Richard W. Lacey
(TECHNICIAN)