

1-060255

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,424 - 0000
NW NW SE, SEC. 8 ; T 26 S, R 12 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

2310 feet from NW/S section line

2310 feet from NW/E section line

Operator: F & M Oil Co., Inc.

Lease Name Schiewe "C" Well # 1

Name & Address 422 Union Center

County Pratt

Wichita, KS 67202

Well Total Depth 4390 ^{142.68} feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Union Drilling Co., Inc. License Number 5103

Address 422 Union Center, Wichita, KS 67202

Company to plug at: Hour: 12:30 pm Day: 29 Month: June Year: 19 84

Plugging proposal received from T. F. Brown

(company name) Union Drilling (phone) 316-262-1872

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 4380' with 50 sx cement

2nd plug at 740' with 50 sx cement

3rd plug at 320' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement. Plugging Proposal Received by Paul A. Luther

(TECHNICIAN)

Plug water well with 5 sx cement

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 2:30 pm Day: 29 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 4380' with 50 sx cement, 2nd plug at 740' with 50 sx

cement, 3rd plug at 320' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement, 7th plug to circulate mouse hole with 10 sx cement and plugged water well

with 5 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this report)

operator (license) observe this plugging.

JUL 06 1984

7-6-84
CONSERVATION DIVISION
Wichita, Kansas

Signed Paul A. Luther
(TECHNICIAN)

INVOICED

DATE 7-16-84

INV. NO. 2493

6-29