

15-151-21407-0000

1 040196

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- NA  
SE SW NE, SEC. 8, T 26 S, R 12 W/E

TECHNICIAN'S PLUGGING REPORT  
Operator License # 32431-FL 5 1988

2970 feet from S section line  
1650 feet from E section line

Operator: Commonwealth Petroleum  
Name & Address P.O. Box 2458 Hutchinson, KS 67504  
Wichita, Kansas

Lease Name Keller Well # 1  
County Pratt 143.16

Well Total Depth 4405 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 253

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SHD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 10:30 a.m. Day: 29 Month: 11 Year: 19 88

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service (phone) 316-672-2531

were: 5 1/2" at 3100' PBD 3085' Perfs at 2970, 3050'

1st plug sand back to 2920' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11 a.m. Day: 29 Month: 11 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 2920' and dumped 5 sx cement on top of  
sand through bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,  
100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 1812' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE DEC 8 1988

Signed Stephen J. Pfeifer  
(TECHNICIAN)

INV. NO. 23286