

1 080235

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,663-00-00

C NE SW, SEC. 6, T 35 S, R 20 W/E  
1980 feet from ~~XXX~~ SE Corner of section line  
3300 feet from ~~XXX~~ SE Corner of section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Tuttle 'E' Well # 1

Operator: Donald C. Slawson

County Comanche

Name & Address 200 Douglas Building

Well Total Depth 4630 <sup>150.48</sup> feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 821

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rine Drilling Co. License Number 5654

Address 300 West Douglas, Suite 600, Wichita, KS 67202

Company to plug at: Hour: 11:00 pm Day: 11 Month: October Year: 19 84

Plugging proposal received from Bob Norveil

(company name) Rine (phone) 316-267-1333

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1300' with 50 sx cement

2nd plug at 870' with 50 sx cement

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by J. H. Metz  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 1:00 am Day: 12 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1300' with 50 sx cement, 2nd plug at 870' with 50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate mouse hole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 19 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton CONSERVATION DIVISION  
(If additional description is necessary, use BACK of this form.) Wichita, Kansas

INVOICED (did not) observe this plugging.

DATE 10-29-84

Signed J. H. Metz  
(TECHNICIAN)

INV. NO. 4522

10-12