

To: 1 051617 2-2  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-033-20,539-00-00 SR  
C SE SE, SEC. 34, T. 33 S, R. 20 W. XX  
660 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30972  
Operator: Bishop Operating Co., Inc.  
Name: Bishop Operating Co., Inc.  
Address P.O. Box 1807  
Hutchinson, KS 67502

Lease Name Selzer Well # 3-34  
County Comanche  
Well Total Depth 4809 156.29 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 703

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635  
Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 10 a.m. Day: 2 Month: 2 Year: 19 93

Plugging proposal received from Gary Burke  
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 4809' with 200 sx cement, Perfs at 4159-68, 4751-54'  
1st plug sand back to 4109' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 11:15 a.m. Day: 2 Month: 2 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded back to 4109' and dumped 5 sx cement on top of sand  
through bailer,  
2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"  
wiper plug and pumped 125 sx cement.  
Maximum pressure 500 psi and shut in 375 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3175' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

~~I did not observe this plugging.~~

DATE 3-3-93  
INV. NO. 37434

Signed Richard W. Lucas  
(TECHNICIAN)