

To: 1 051616 2-2  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,569-06-00 9 R  
C SW SE, SEC. 34, T 33 S, R 20 W/R

TECHNICIAN'S PLUGGING REPORT

Operator License # 30972

Operator: Bishop Operating Co., Inc.  
Name & Address P.O. Box 1807  
Hutchinson, KS 67502

660 feet from S section line  
1980 feet from E section line  
Lease Name Baker Well # 1-34  
County Comanche  
Well Total Depth 4820 156.65 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 684

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635  
Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 2 Month: 2 Year: 19 93

Plugging proposal received from Gary Burke  
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

Work: 5 1/2" at 4819' w/200 sx cement, PBTD 4802', Perfs at 4743-61'  
1st plug sand back to 4693' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 10 a.m. Day: 2 Month: 2 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4693' and dumped 5 sx cement on top of sand through bailer,  
2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"  
wiper plug and pumped 125 sx cement.  
Maximum pressure 600 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3364' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)  
**INVOICED**  
I (did / ~~did not~~) observe this plugging.  
DATE 3-3-93  
WELL NO. 37433  
Signed Richard W. Loney  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 24 1993  
CONSERVATION DIVISION  
WICHITA, KANSAS