

To: 1 051212
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-6
API NUMBER 15-033-20,669-00-00

NW NW SW, SEC. 12, T 35 S, R 20 W/E

2310 feet from S section line

4950 feet from E section line

Lease Name Box Ranch Well # 1-12

County Comanche 219.40

Well Total Depth 6751 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 901

TECHNICIAN'S PLUGGING REPORT

Operator License # 4145

Operator: Roberts & Murphy, Inc.

Name & Address P.O. Box 7125

Shreveport, LA 71137-7125

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 9 a.m. Day: 6 Month: 10 Year: 19 89

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 6750' PBTD 6694' Perfs at 6422-53'

1st plug pump 200 lbs. hulls and 25 sx cement, push plug to 6000' with mud, pump through casing:

2nd plug at 950' with 50 sx cement,

3rd plug at 400' with 35 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 3 p.m. Day: 6 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement to 6000'

Pumped through casing,

2nd plug at 950' with 50 sx cement,

3rd plug at 400' with 35 sx cement,

4th plug at 40' with 10 sx cement.

Remarks: Used common cement by Sargent's. Recovered 3615' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

(If a representative observe this plugging.

INVOICED

DATE 10-13-89

Signed Richard W. Lacy (TECHNICIAN)

INV. NO. 26144

10-6

RECEIVED
STATE CORPORATION COMMISSION
OCT 12 1989