

To: 1-051517
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-033-20,672-00-00 1-9-92 26 P

TECHNICIAN'S PLUGGING REPORT

Operator License # 4145

Operator: Roberts & Murphy, Inc.

Name & Address P.O. Box 7125

Shreveport, LA 71137-7125

4950 feet from S section line

3080 feet from E section line

Lease Name Box Ranch Well # 1-14

County Comanche 222.62

Well Total Depth 6850 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 855

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 5 p.m. Day: 9 Month: 1 Year: 19 92

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service (phone) 316-672-5901

were: 5 1/2" at 5500' w/220 sx cement, PBSD 5481', Perfs at 5324-36, 5381-86'

1st plug set CIBP at 5250' and dump 2 sx cement on top,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 150 sx cement.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 6:30 p.m. Day: 9 Month: 1 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5250' and dumped 2 sx cement on top,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 145 sx cement.

Maximum pressure 1300 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2763' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED
OBSERVE THIS PLUGGING.

DATE 1-17-92 JAN 13 1992

Signed Richard W. Lacy
(TECHNICIAN)

WICHITA, KANSAS
CONSERVATION DIVISION
WICHITA, KS