

1 030654

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,761-³³⁹~~00-00~~ R

SE SE SE, SEC. 4, T 26 S, R 11 (W/E)
330 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Zink "A" Well # 1

Operator: TXO Production Corporation
Name & Address 155 North Market, Suite 1000
Wichita, KS 67202

County Pratt 135.53

Well Total Depth 4170 Mississippi feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 443

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor FWA Drilling Co., Inc. License Number 6165

Address P. O. Box 970, Yukon, OK 73099

Company to plug at: Hour: 1:00 am Day: 30 Month: January Year: 19 86

Plugging proposal received from Gerald Veatch

(company name) TXO (phone) 405-354-5209

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1858' KB
Anhydrite 885'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 30' below the base of the surface pipe with 50 sx cement
solid bridge

3rd plug hulls + plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Richard W. Lacey

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:30 am Day: 30 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 900' with 50 sx cement, 2nd plug at 470' with 50
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate

mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB 4 1986

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED

(date) did not observe this plugging.
FEB 6 1986

Signed Steve Demont
(TECHNICIAN)

DATE

INV. NO. 12420