

1 050211

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,395-00-00

NW NE NW, SEC. 8, T. 26 S, R. 11 W

330 feet from N/SX section line

1650 feet from W/EX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Huff Well # 2-8

Operator: Texas Energies, Inc.

County Pratt

Name & Address P. O. Box 947

Well Total Depth 4250 138.13 feet

Pratt, KS 67124

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 351

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Wheatstate Oilfield Services License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: Midnight Day: 5 Month: May Year: 19 84

Plugging proposal received from Dennis Petz

(company name) Wheatstate (phone) 316-672-7514

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 720' with 50 sx cement

2nd plug at 390' with 40 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement

6th plug to circulate mousehole with 10 sx cement, Plug water well with 5 sx cement
Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:00 am Day: 5 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 720' with 50 sx cement, 2nd plug at 390' with 40
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with
10 sx cement, 5th plug to circulate rathole with 15 sx cement, 6th plug to circulate
mousehole with 10 sx cement, plug water well with 5 sx cement

RECEIVED
STATE CORPORATION COMMISSION

MAY 11 1984

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Use 60/40 Pozmis 2% gel 3% cc by Halliburton
(If additional description is necessary, use BACK of this form.)

INVOICED

(check) did not observe this plugging.

DATE 5-15-84

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 1511

5-5