

1 030946

5-23-88

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-151-21,883-00-00

NW SW SW, SEC. 8, T 26 S, R 11 W/X  
990 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5923  
Operator: American Petroleum Company, Inc.  
Name & Address: 3500 North Rock Road, Bldg. 1300  
Wichita, KS 67226

Lease Name Jorns Well # 1  
County Pratt 139.26  
Well Total Depth 4285 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 248

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Eagle Drilling Inc. License Number 5380  
Address Box 8609, Wichita, KS 67208

Company to plug at: Hour: 6 a.m. Day: 23 Month: 5 Year: 19 88

Plugging proposal received from Butch Steinert

(company name) Eagle Drilling Inc. (phone) 316-945-9935

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1855'  
Anhydrite 680'

- 1st plug at 690' with 50 sx cement, 2nd plug at 270' with 40 sx cement,
- 3rd plug at 40' with 10 sx cement,
- 4th plug to circulate rathole with 15 sx cement,
- 5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 8:45 a.m. Day: 23 Month: 5 Year: 19 80

ACTUAL PLUGGING REPORT 1st plug at 690' with 50 sx cement,

- 2nd plug at 270' with 40 sx cement,
- 3rd plug at 40' with 10 sx cement,
- 4th plug to circulate rathole with 15 sx cement,
- 5th plug to circulate mousehole with 10 sx cement,
- Water well plugged with 10 sx cement.

RECEIVED STATE CORPORATION COMMISSION

MAY 24 1988

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.  
(If additional description is necessary, use BACK of this form.)

INVOICED (If not observed this plugging.)

DATE 5-25-88  
INV. NO. 20868

Signed Steve Durrant (TECHNICIAN)