

To: 1 120825 9-20
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-22,012-00-00
250' S of
NE NE SW, SEC. 8, T 26 S, R 11 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3180
Operator: Deutsch Oil Company
Name:
Address 107 N. Market, Ste. 1115
Wichita, KS 67202

2060 feet from S section line
2970 feet from E section line
Lease Name Jorns Well # 1-8
County Pratt 138.12
Well Total Depth 4250 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 285

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor DS&W Well Servicing Co. Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 12:15 p.m. Day: 20 Month: 9 Year: 19 93

Plugging proposal received from Kent Deutsch
(company name) Deutsch Oil Co. (phone) 316-267-7551

were: 4 1/2" at 4240' with 150 sx cement, Perfs at 4132-62'
1st plug sand back to 50' above perfs with 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 1:45 p.m. Day: 20 Month: 9 Year: 19 93.

ACTUAL PLUGGING REPORT 1st plug sanded back to 4080' and dumped 4 sx cement on top of sand through bailer,
2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"
wiper plug and pumped 100 sx cement.
Pumping pressure 0-300 psi and shut in 100 psi.

RECEIVED
STATE CORPORATION COMMISSION
SEP 29 1993
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1725' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

DATE 10-4-93
OBSERVE this plugging.
INV. NO. 38845
9-20

Signed Duane Rankin
(TECHNICIAN)