

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-00213-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 3-34S-11W
330 feet from N Section Line, 2310 feet from E Section Line
Lease Name: FINNUP B Well #: 1-3
County: BARBER Total Vertical Depth: 4685 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4438		WITH 2 SX CMT
PROD	5.5	4680	1741	WITH 100 SX CMT
SURF	8.625	265		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/02/2014 12:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: SET CIBP @ 4430' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 09/02/2014 1:20 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4438' WITH 2 SX CMT. 1ST PLUG AT 623' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 311' WITH 50 SX CMT. 3RD PLUG AT 62' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4488	4504		

Received
KANSAS CORPORATION COMMISSION
SEP 12 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
SEP - 5 2014
KCC DODGE CITY

9.17.14 C/KM

[Signature]