

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-00192-00-00
Spot: NW Sec/Twnshp/Rge: 35-21S-33W
1320 feet from N Section Line, 1320 feet from W Section Line
Lease Name: SONDEREGGER Well #: 1-35
County: FINNEY Total Vertical Depth: 2712 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2711	0	WITH 300 SX CMT
SURF	8.625	307		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/02/2014 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 160 SX CMT WITH 350# HULLS DOWN CASING. DISPLACE TO 1200' WITH WATER. RUN CBL TO DETERMINE TOC. PERFORATE AND/OR RUN TBG AS REQUIRED.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/02/2014 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 160 SX CMT WITH 350# HULLS DOWN THE 5 1/2" CASING. DISPLACE WITH WATER TO 1150'. PRESSURE TEST CASING TO 700#. HOLDING. RUN CBL FROM 1150' TO 40'. TOC BEHIND THE 5 1/2" CASING IS 660'. PERFORATE 4 HOLES AT 350'. RUN TBG TO 1123' & SPOT 75 SX CMT UP TO 350'. TOOH WITH TBG. HOOK UP TO CASING AND CIRCULATE CMT TO SURFACE THROUGH PERFS AT 350' LEAVING THE CASING AND THE ANNULUS FULL OF CMT USING 120 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2638	2694		

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEAE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed Ken Jehlik
9-17-14 kcm (TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

SEP 15 2014

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3