

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-00242-00-00
Spot: NW Sec/Twnshp/Rge: 16-22S-32W
1320 feet from N Section Line, 1320 feet from W Section Line
Lease Name: HETT Well #: 1-16
County: FINNEY Total Vertical Depth: 2960 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2688	0	WITH 300 SX CMT
SURF	8.625	402		WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/02/2014 2:30 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 150 SX CMT WITH 300# HULLS DOWN CASING. DISPLACE WITH WATER TO 1100-1200'. LOG FROM 1100' TO DETERMINE TOC. PERFORATE AND/OR RUN TBG AS NECESSARY.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/02/2014 6:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 150 SX CMT WITH 250# HULLS DOWN CASING. DISPLACE TO 1170' WITH WATER. PRESSURE TEST CASING TO 700#. HOLDING. RUN CBL FROM 1190' TO 20'. TOC OUTSIDE 5 1/2" CASING IS 615'. PERFORATE 4 HOLES AT 420'. RUN TBG TO 1100'. CIRCULATE CMT TO SURFACE UP THE 2 3/8" X 5 1/2" ANNULUS WITH 45 SX CMT THEN THROUGH THE PERFS AT 420 UP THE 5 1/2" X 8 5/8" ANNULUS TO SURFACE WITH 155 SX CMT. TOOH WITH TBG & TOP OFF WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2640	2674		

Received
KANSAS CORPORATION COMMISSION
SEP 12 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed [Signature]
(TECHNICIAN)

9-17-14 ckm

RECEIVED
SEP - 3 2014
KCC DODGE CITY