

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22267-00-00
Spot: SENWSW Sec/Twnshp/Rge: 33-33S-13W
1500 feet from S Section Line, 4325 feet from E Section Line
Lease Name: SPRIGGS B Well #: 2
County: BARBER Total Vertical Depth: 4895 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		800		WITH 2 SX CMT
PROD	4.5	4778	0	WITH 210 SX CMT
SURF	8.625	375		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/28/2014 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: 15 SX CMT AT 1880'. SET CIBP @ 800'. PERFORATE AT 770'. CIRCULATE CMT TO SURFACE LEAVING CASING & ANNULUS FULL OF CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 09/02/2014 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CASING COLLAPSED AT 1880' WITH BAKER RBP AT 2390'. PUMPED 15 SX CMT AT 1800'. SET CIBP @ 800' WITH 2 SX CMT. PERFORATED AT 770' RAN TBG TO 770' & PUMPED 85 SX CMT, CIRCULATING CMT INSIDE OF THE 4 1/2". PULLED TBG & PUMPED 150 SX CMT DOWN THE 4 1/2" CASING. HAD GOOD RETURNS BUT RAN OUT OF CMT. WENT & GOT MORE CMT. PUMPED 50 SX CMT DOWN THE 4 1/2" & PRESSURED TO 500#. TIED ONTO BACKSIDE & PUMPED 80 SX CMT PRESSURING TO 300#. CMT FELL 40' INSIDE 4 1/2" & 116' OUTSIDE 4 1/2". 9/2/14: RAN 1" INSIDE 4 1/2" & FILLED TO SURFACE WITH CMT. RAN 1" DOWN 4 1/2" X 8 5/8" ANNULS & FILLED WITH CMT. USED TOTAL OF 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4778	4895		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 01

Signed *Ken Jehlik*
(TECHNICIAN)

RECEIVED
SEP - 5 2014
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION
SEP 15 2014
CONSERVATION DIVISION
WICHITA, KS

9.17.14 CM
Form CP-2/3