

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

JUN 3 1963

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Herb Mason of Dunne-Gardner Co. Inc. has this

date requested permission to plug the following described well:

Mr. Mason guarantees payment of the plugging fee.

Operator's full Name: Dunne - Gardner Co. Inc.

Complete Address: 300 Schweiter Bldg., Wichita, Kansas

Lease Name: Ohley Well No. # 1

Location: SE NE SE Sec. 23 Twp. 26 Rge. 14 (E) (W) W

County Pratt Total Depth 4559 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Mason was instructed to plug the well as follows:

598' of 8 5/8" surface pipe, cement circulated with 600  
sacks. Fill hole with mud to 240', 1st cementing plug,  
1/4 sack hulls, cement with 20 sacks. Fill hole with mud  
to 40', 2nd cementing plug, 1/4 sack hulls, cement with  
10 sacks to base cellar. Bridge and cement rat hole with  
2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent