

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 29 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill,  
filed September 7, 1967.

Dear Sir:

Mr. Gerd Steincamp of Strata Drilling, Inc. has this  
date requested permission to plug the following described well:

Mr. Steincamp guarantees payment of the plugging fee.

Operator's full Name: Strata Drilling, Inc.

Complete Address: P. O. Box 355, Great Bend, Kansas 67530

Lease Name: Schoonover Well No. # 1

Location: NE NW Sec. 29 Twp. 26 Rge. 14 (E)(W) W

County Pratt Total Depth 4650' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Steincamp was instructed to plug the well as follows:

333' of 8 5/8" surface pipe, cement circulated with 220 sacks. Fill  
hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack  
of huls, and cement with 25 sacks. Fill hole with drilling mud to 40',  
2nd cementing plug, bridge with 1/2 sack of huls, and cement with 10  
sacks to base of cellar. Bridge and cement rat & mouse holes with 4 sack

Very truly yours,

Arlie Elving  
Conservation Division Agent