

State of Kansas



FORM - CP-2

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSASVERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSION

JUN 8 1964

CONSERVATION DIVISION  
Wichita, KansasJ. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Bill Walker of Rains & Williamson Oil Co has this  
date requested permission to plug the following described well:Mr. Walker guarantees payment of the plugging fee.Operator's full Name: Rains & Williamson Oil CompanyComplete Address: 1425 Wichita Plaza, Wichita, KansasLease Name: Fulks Well No. # 1Location: C SE NE Sec. 2 Twp. 26 Rge. 11 (E) (W) WCounty Pratt Total Depth 4486 Oil Well Gas Well  Input Well  SWD Well  D & A X Lost Hole Mr. Walker was instructed to plug the well as follows:

259' of 8 5/8" surface pipe, cemented with 170 sacks. Fill  
hole with drilling mud to 250', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drill-  
ing mud to 40', 2nd cementing plug, bridge with hulls, and  
cement with 10 sacks to base cellar. Bridge and cement rat  
hole with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent