

State of Kansas



GEORGE DOCKING Governor
 MARION BEATTY Chairman
 HARRY G. WILES Commissioner
 RICHARD C. BYRD Commissioner
 RAYMOND B. HARVEY Secretary
 CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

Jewel M. Ogden, Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date 24 December, 19 58, authorized the following plugging operation:

Operator's Full Name: Mull Drilling Co., Inc.

Complete Address: Wichita, Kans.

Lease Name: McAhren Well No. 1

Location: SW SW NE Sec. 26 Twp. 26 Rge. 15 (E) (W) X

County: Pratt Total Depth: 4463

Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

830' of 8 5/8" surface casing circulated with cement. Fill
hole to 300' with heavy drilling mud. Set cementing plug at
300' and place 20 sack cement top plug through drill pipe.
Heavy drilling mud to 35'. Place cementing plug at 35' and
cement to base of cellar.

Very truly yours,

Signed: [Signature]
 Conservation Division Agent