

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

R
 VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUN 10 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Ralph Schuyler of Strata Drilling Co. has this
 date requested permission to plug the following described well:

Mr. Schuyler guarantees payment of the plugging fee.

Operator's full Name: Strata Drilling Co.

Complete Address: Box 355, Great Bend, Kansas

Lease Name: Curtis Well No. # 3

Location: SW SE NW Sec. 26 Twp. 26 Rge. 15 (E) (W) W

County Pratt Total Depth 4657 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Schuyler was instructed to plug the well as follows:

400' of 13 3/8" surface pipe, cement circulated with 425
sacks. Fill hole with mud to 240', 1st cementing plug,
1/2 sack hulls, cement with 30 sacks. Fill hole with mud
to 40', 2nd cementing plug, 1/2 sack hulls, cement with
18 sacks. Rat hole bridged and cemented with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent