

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

MAY 21 1963

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts.  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Ralph Schuyler of Strata Drilling Co. Inc. has this

date requested permission to plug the following described well:

Mr. Schuyler guarantees payment of the plugging fee.

Operator's full Name: Strata Drilling Co. Inc.

Complete Address: Box 355, Great Bend, Kansas

Lease Name: Curtis Well No. # 1

Location: C SE NW Sec. 26 Twp. 26 Rge. 15 (E) (W) W

County Pratt Total Depth 910 Oil Well     

Gas Well      Input Well      SWD Well      D & A      Lost Hole X

Mr. Schuyler was instructed to plug the well as follows:

272' of 10<sup>3</sup>/<sub>4</sub>" surface pipe, cement circulated. Set solid plug  
at 200', with rock bridge, cement with 25 sacks. Fill hole  
with mud to 40', 2nd cementing plug,  $\frac{1}{4}$  sack hulls, cement  
with 15 sacks to base cellar. Rat hole bridged and cemented  
with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent