

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

MAY 27 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts.
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Ralph Schuyler of Strata Drilling Co. Inc. has this
 date requested permission to plug the following described well:

Mr. Schuyler guarantees payment of the plugging fee.

Operator's full Name: Strata Drilling Co. Inc.

Complete Address: Box 355, Great Bend, Kansas

Lease Name: Curtis Well No. # 1

Location: C SE NW Sec. 26 Twp. 26 Rge. 15 (E) (W) W

County Pratt Total Depth 782 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole X

Mr. Schuyler was instructed to plug the well as follows:

Circulation was lost and tools was stuck in sand at 782',
drilling hole for surface pipe. Pipe was shot off at 390',
Hole will be plugged and rig skidded.

Set solid bridge at 200', cement with 30 sacks. Fill hole
with mud to 40', set bridge and cement with 20 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent