

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
 WILLIAM L. MITCHELL, Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

AUG 17 1964

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Claude Boman of Tomilson and Kathol Inc. has this date requested permission to plug the following described well:

Mr. Boman guarantees payment of the plugging fee.

Operator's full Name: Tomilson and Kathol Inc.

Complete Address: 1125 Wichita Plaza, Wichita, Kansas

Lease Name: Tatlock Well No. # 1

Location: C NW NW Sec. 29 Twp. 26 Rge. 15 (E) (W) W

County Pratt Total Depth 4690 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Boman was instructed to plug the well as follows:

340' of 8 5/8" surface pipe, cement circulated with 275 sacks.

Fill hole with drilling mud to 250', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling

mud to 40', 2nd cementing plug, bridge with hulls, and cement

with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving