

State of Kansas



FORM - CP-2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSASVERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

APR 7 1964

CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Howard Roberts of Strata Drilling Inc. has this
date requested permission to plug the following described well:Mr. Roberts guarantees payment of the plugging fee.Operator's full Name: Time Petroleum Company
NationalComplete Address: 815 Union ~~Center~~ Bldg., Wichita, KansasLease Name: Curtis "B" Well No. # 1Location: C NE NE Sec. 15 Twp. 26 Rge. 15 (E) (W) WCounty Pratt Total Depth 4365 Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Roberts was instructed to plug the well as follows:

377' of 8 5/8" surface pipe, cemented with 350 sacks. Fill
hole with drilling mud to 370', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drill-
ing mud to 40', 2nd cementing plug, bridge with hulls, and
cement with 10 sacks to base cellar. Bridge and cement rat
hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent