

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Howard Roberts of Strata Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Roberts guarantees payment of the plugging fee.

Operator's full Name: U. S. Hydrocarbon Company

Complete Address: 815 Union National Bldg., Wichita, Kansas

Lease Name: Kearns Well No. # 1

Location: C SW NW Sec. 12 Twp. 26 Rge. 15 (E)(W) W

County Pratt Total Depth 3860' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Roberts was instructed to plug the well as follows:

305' of 8 5/8" surface pipe, cement circulated with 325 sacks. Fill hole with drilling mud to 295', 1st cementing plug, bridge with 1/4 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sack. Bridge and cement mouse hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION  
APR 25 1966  
CONSERVATION DIVISION  
Wichita, Kansas