

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

FEB 7 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. George Day of Stickle Drilling Company has this date requested permission to plug the following described well:

Mr. Day guarantees payment of the plugging fee.

Operator's full Name: Stickle Drilling Company

Complete Address: 1100 Bitting Bldg., Wichita, Kansas

Lease Name: Koenemann Well No. # 1

Location: SW NE NW Sec. 28 Twp. 26 Rge. 11 (E)(W) W

County Pratt Total Depth 4500' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Day was instructed to plug the well as follows:

250' of 8 5/8" surface pipe, cement circulated with 200 sacks.

Fill hole with drilling mud to 250', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat and mouse holes with 4 sacks.

Very truly yours,

Arlene Elving
Conservation Division Agent