

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Shawn of Sage Drlg. Co. Inc. has this
date requested permission to plug the following described well:

Mr. Shawn guarantees payment of the plugging fee.

Operator's full Name: Jack R. Sowles & John B. McCloud

Complete Address: 2426 N.E. Broadway Portland OR

Lease Name: Woods B Well No. 1

Location: C/SE/SW Sec. 3 Twp. 26s Rge. 13 (E)(W) W

County: Pratt Total Depth Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Shawn was instructed to plug the well as follows:

497 ft of 8 5/8 surface pipe cemented with 450 sacks. Fill
hole to 450 ft, 1/2 sack hulls, plug, 35 sacks cement. Mud
to 40 ft, 1/2 sack hulls, plug, 10 sacks cement to surface.
2 sacks cement in rat hole.

Very truly yours,

Ad Russell Bibeau
Conservation Division Agent