

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 CONSERVATION DIVISION
 OCT 21 1966
 CONSERVATION DIVISION
 WICHITA, KANSAS

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Dale Buller of Gabbert-Jones, Inc. has this
 date requested permission to plug the following described well:

Mr. Buller guarantees payment of the plugging fee.

Operator's full Name: J. Mark Richardson

Complete Address: 502 Union Center Bldg., Wichita, Kansas

Lease Name: Woods Well No. # 1

Location: C S/2 NW Sec. 2 Twp. 26 Rge. 13 (E)(W) W

County Pratt Total Depth 4470' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Buller was instructed to plug the well as follows:

331' of 8 5/8" surface pipe, cement circulated with 300 sacks. Fill
hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to the base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Arlene Elving
 Conservation Division Agent