

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

DEC 7 1962

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dec. 4, 1962.

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Otto L. Berens of Rex & Morris & Herndon Drlg. Co. this
 date requested permission to plug the following described well:

Mr. Otto Berens guarantees payment of the plugging fee.

Operator's full Name: Rex & Morris & Herndon Drlg., Co.

Complete Address: Box 334, El Dorado, Kansas.

Lease Name: Bauman #1 Well No. #1

Location: C-SW-NW Sec. 10 Twp. 26S Rge. 11(E) (W) X

County Pratt County Total Depth 4425' Oil Well _____

Gas Well _____ Input Well _____ SWD Well _____ D & A X Lost Hole _____

Mr. Otto Berens was instructed to plug the well as follows:

247' of 8 5/8" surface pipe circulated with 200 sacks cement.

Hole filled to 180' with heavy drill mud, 1 sack hulls, 1st

cementing plug and 20 sacks cement. Hole filled to 40' with

heavy drill mud, 1 sack hulls, 2nd cementing plug and 10

sacks cement to base of cellar. Rat hole bridged and 2
sacks cement.

Very truly yours,

Harman Justus
 Conservation Division Agent