

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
3-4-70
MAR 4 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Austin Gas Purchasing In.

Complete Address Box 159 Stafford, Ks 67578

Lease Name Petrowsky Well No. 1

Location SW/NW/NW Sec. 29 Twp. 26 Rge. 12 (E) (W) X

County Pratt Total Depth 4303

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Ks 67524 License No. 436

Operation Completed: Hour 4:00PM Day 2 Month 3 Year L970

The above well was plugged as follows:

357 ft. of 8 5/8 surface pipe circulated with cement. 4300 ft of
5 1/2 long string. Top Perf. 2414 ft. Sand back to 2660 ft, 5 sacks c
ement with bailer. Mud to 310 ft, 10 ft rock bridge, 25 sacks
cement. Mud to 40 ft, 10 ft rock bridge. 10 sacks cement to surface.
2000 ft. of 5 1/2 pulled.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 3/4/70

INV. NO. 1543-W