

15-151-30171-00-01

Form CP-3  
Rev. 6-26-62

*RP*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

JAN 2 1963  
1-2-63  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Champlin Oil & Refining Co.

Complete Address: P. O. Box 308 Ellinwood, Kansas.

Lease Name Stueder #1 Well No. #1

Location SW-SE-SW Sec. 29 ~~25~~ Twp. 26 Rge. 12 (E) (W) X

County Pratt Total Depth 4299'

Abandoned Oil Well X & Gas Well X Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Glenn & Smith Pipe Pulling Co.

Address: 204 E. 6th Ellinwood, Kansas. License No.     

Operation Completed: Hour 10:AM Day 20 Month Dec. Year 1962

The Above well was plugged as follows:

4299' of 5 1/2" oil string cemented with 250 sacks cement. plugged back  
to 2446' . Top perforation at 2413'. Sanded to 2400' & 5 sacks cement.  
545' of 10 3/4" surface pipe circulated with cement. Hole filled to 500'  
with heavy mud, 10' rock bridge and 25 sacks cement. Hole filled to 40'  
with heavy mud, 10' rock bridge & 10 sacks cement to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Robert M. Justice*  
Well Plugging Supervisor

DATE 1/4/63  
INV. NO. 6369-U