

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 8 1965
3-8-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name R. W. Rine Co. (& Wayne E. Walcher & Shell Oil Co.)

Complete Address: 420 Union Center, Wichita, Kansas

Lease Name Brown Well No. # 1

Location C S/2 SE Sec. 29 Twp. 26 Rge. 12 (E) (W) W

County Pratt Total Depth 2580'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 10:00AM Day 7th Month March Year 1965

The Above well was plugged as follows:

354' of 8 5/8" surface pipe, cemented with 300 sacks. 2475' of 5 1/2" long string, cemented with 250 sacks. Plug back to 2423'. Top perforation 2407'.

All perforation were squeezed with 75 sacks of cement, by Halliburton cementing Co., bringing the top of the cement to 1897'. 1420' of 5 1/2" long string was recovered from the hole. Fluid was up in the hole. Bridge plug was pushed in fluid to 275', and 10' of rock bridge. 5 sacks of cement was mixed in barrel,

and put on plug at 265', through the dump bailer, and let set over-night. Next morning hole was bailed dry, and 20 sacks of cement was added to the plug. Hole was filled with mud to 40', and 10' of rock bridge, and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/8/65

INV. NO. 786-W

Signed: Archie Elving
Well Plugging Supervisor