

Y KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 31 1962
10-31-62
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Musgrove Drilling & Petroleum Associates Fund

Complete Address: 801 Union Center Wichita, Kansas.

Lease Name Hartsell #2 Well No. #2

Location C-N $\frac{1}{2}$ -Lot3 Sec. 3 Twp. 26 Rge. 12 (E) (W) X

County Pratt Co. Total Depth 4259'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Bowers Drilling Co. Inc.

Address: Union Center Bldg. Wichita, Kansas. License No. _____

Operation Completed: Hour 5:30AM Day 28 Month Oct. Year 1962

The Above well was plugged as follows:

390' of 8 5/8" surface pipe circulated with 275 sacks cement. Hole filled to 160' with heavy drill mud, $\frac{1}{2}$ sack hulls, 1st cementing plug and 20 sacks cement. Hole filled to 40' with heavy drill mud, $\frac{1}{2}$ sack hulls, 2nd cementing plug, 10 sacks cement to base of cellar. Rat hole bridged and 2 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/1/62
INV. NO. 5945-W

Signed: Herman Justice
Well Plugging Supervisor