

15-151-10934-00-02

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 128-19 County: Pratt

Location: NE NE NW Sec. 36 Twp. 26 Rge. 13 (E) (W) X

Name of Field: _____ Total Depth: 4336

I have this date completed supervision of plugging of:

Lease Name: Geissler Well No. 1

Operator's Full Name: Forbes Casing Pulling Co.

Complete Address: Box 221, Great Bend, Kans.

Plugging Contractor: Same

Address: _____ License No. _____

Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes ___ No X

If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 14 Month September Year 1958

The above well was plugged as follows:

808' of 8 5/8" surface casing circulated with cement. Hole was sanded to
3955 and 5 sack cement dumped with dump bailer. Hole was loaded with heavy
mud and 2000' of pipe pulled. Hole filled to 250' with heavy mud with rock
bridge set from 350'. 20 sack cement placed from 350'. Heavy mud to 35'.
Rock bridge set from 35', with 10 sack cement to base of cellar.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

PLUGGING
FILE SEC 36 Twp R13W
BOOK PAGE 122 LINE 19

RECEIVED
STATE CORPORATION COMMISSION
SEP 20 1958
9-20-58
CONSERVATION DIVISION
Wichita, Kansas