

KANSAS

Form CP-3  
Rev. 6-4-68

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

APR 30 1975

CONSERVATION DIVISION  
Wichita, KansasJ. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Thunderbird Drilling, Inc.

Complete Address Box 18407, Wichita, Kansas 67218

Lease Name Horchem "C" Well No. 2

Location NW SW SW Sec. 19 Twp. 16 Rge. (E) (W) 26

County Ness Total Depth 4556'

Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Knight Casing Pulling

Address Box 405, Chase, Kansas 67524 License No. 436

Operation Completed: Hour 2 P Day 28 Month 4 Year 1975

The above well was plugged as follows:

Total Depth 4556' 8 5/8 csg set at 334' cwc 225 sx.

5 1/2 csg set 4548' cw 100 sx cem. & perf. (4180)

Set 5 1/2 wood plug at 4160' -poured 10' sd -dumped 5 sk cem. W/dump bailer. (4160-4115)

Cutoff & recovered 1642' of 5 1/2 csg.

Mixed & pumped down 8 5/8 csg with 22 sx gel & water W/100 lbs hulls -released plug  
& 100 sk 50-50 poz 6% -displaced with 8 sk gel & water & capped with 20 sk 50-50 ~~poz~~  
poz 6% by Allied Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Marney  
Well Plugging Supervisor

INVOICED

DATE 5/7/75INV. NO. 1269-W