

KANSAS

af STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 9 1973
7-9-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Specter Pipe & Supply Inc

Complete Address Box 169 Russell, KS

Lease Name Davis Ranch O Well No. 1

Location NW/SW/NW Sec. 5 Twp. 34 Rge. 14 (E) (W) W

County Barber Total Depth 4880

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Co Inc

Address Box 364 Great Bend, KS License No. 399

Operation Completed: Hour 4:00 PM Day 6 Month 7 Year 1973

The above well was plugged as follows:

201 ft 13 3/8 surface cemented with 225 sacks. 4878 ft 4 1/2 long string
cemented with 50 sacks. Top perf. 4826 ft. Sand to 4800 ft., 4 sacks
cement with bailer. Pulled 4000 ft 4 1/2. Set 20 ft rock bridge at
120 ft. Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *J. Russell Biberstein*
Well Plugging Supervisor

DATE 7/10/73

INV. NO. 7611-W