

15-087-16674-0000

Form CP-3
Rev. 6-4-68

KANSAS

M STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 23 1973
7-23-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Specter Pipe & Supply Inc

Complete Address Box 169 Russell, KS

Lease Name Davis Ranch G Well No. 2

Location C SW/SE Sec. 5 Twp. 34 Rge. 14 (E) (W) W

County Barber Total Depth 4830

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Co Inc

Address Box 364 Great Bend, KS License No. 399

Operation Completed: Hour 5:00 PM Day 19 Month 7 Year 1973

The above well was plugged as follows:

953 ft 8 5/8 surface cement circulated. 200 ft 13 3/8 surface cemented

with 300 sacks. 4828 ft 5 1/2 long string cemented with 150 sacks.

Open hole. Sand to 4800 ft, 5 sacks cement with bailer. Pulled

467 ft 8 5/8. Pulled 3824 ft 5 1/2. Set 20 ft rock bridge at 120 ft.

Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *D. Russell Biberstein*
Well Plugging Supervisor

DATE 7/24/73

INV. NO. 9075-W