

KANSAS  
STATE CORPORATION COMMISSION

R

CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Barber

Location: Center SE-NW-NE Sec. 5 Twp. 35 Rge. 12 (E) W (W) \_\_\_\_\_

Name of Field: Hardtner Total Depth: 4940'

I have this date completed supervision of plugging of:

Lease Name: Barbara-Amerada Bank Unit Well No. 1

Operator's Full Name: Barbara Oil Company-

Complete Address: 322 Central Builing, Wichita 2, Kansas

Plugging Contractor: Arnett Casing Pulling Company

Address: Hoisington, Kansas License No. \_\_\_\_\_

Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A ~~Yes~~ X

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 2:30 PM Day 16 Month June Year 1958

The above well was plugged as follows:

Lane Wells bridge plug set at 4850'. Filled with gravel from 4850' to 4768'.  
Mixed and dumped with bailer 6 sacks of cement. Top of cement at 4715'. Shot casing  
at 3495', pulled 40 joints at approx. 1720'. Mixed and circulated 80 sks. of Magcogel  
mud at 1775', Good circulation of mud in cellar. Finished pulling casing. 8 5/8" surface  
casing set at 286' cemented top to bottom. Bailed mud to 286', set 10' rock bridge  
from 286' to 276'. Mixed and dumped 25 sacks cement. Filled with mud to 40' below  
base of cellar. Rock bridge from 40' to 30'. Mixed and dumped 10 sacks cement to base  
of cellar.

Signed: [Signature]  
Conservation Division Agent

Reviewed: J. Lewis Brock  
Field Supervisor

Remarks:

PLUGGING  
FILE SEC 5 T 35 R 12W  
BOOK PAGE 101 LINE 23

6-25-58